Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
4	Code No.: 3008 Providing 250mm dia PVC Pipe 10kg/cm **Page No. XXXV, Sl No. 892 PWD SR 2018-19**	Rmtr							.0
			2	30.00			**60.00**	2203.39	**132203.00**
5	Providing and fixing Borewell Cap and Clamp Set **Page No. XLVII, Sl No. 17 PWD SR 2018-19**	Set							
			2				**2**	1800.00	**3600.00**
6	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps **PWD SR 2018-19 P. XLII Item No. 51**	No						
	17.5 HP 40 Stage		2				**2**	78036.00	**156072.00**
7	Providing GI Pipe 50 mm 'B' Class **Page No. XLVII, Sl No. 1 PWD SR 2018-19**	m							
			2	280.00			**560.00**	415.00	**232400.00**
8	Providing Collar 50 mm **Page No. XLVII, Sl No. 1 PWD SR 2018-19**	No							
			2x47				**94**	180.00	**16920.00**
9	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of **Sub mersible cable 1x3x6.00 Sq.mm Page No. XLVII, Sl No.8, PWD SR 2018-19**	Mtr							
			2x2	290.00			**1160.00**	144.00	**167040.00**
10	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) **Page No. 558, Items No-3 BWSSB SR for 2014-15)**	Per Length							
	(270/6)=45.00		2	47.00			**47**	88.00	**4136.00**